

## Lexus

<b>Tuft gauge</b>	1/10 cut pile	
<b>Pilecomposition</b>	100% PES	
<b>Primary Backing</b>	Woven	
<b>Secondary backing</b>	AB Duo Backing	
<b>Width</b>	400 cm, 500 cm	± 1%
<b>Pile height</b>	16 mm	
<b>Pile Density</b>	ca 0.130 gr/cm3	
<b>Pile Weight</b>	2350 gr/m2	
<b>Total weight</b>	3070 gr/m2	± 15%
<b>Total Height</b>	18 mm	
<b>Number of knots</b>	233000 /m2	-7.5% .+10%
<b>Use Area</b>	Intensiv (32)	
<b>GUT Nr.</b>	2A7F06BD GUT	
<b>Light fastness</b>	≥ 5	
<b>Wearebility</b>	≥ 4	
<b>Water fastness</b>	≥ 4	
<b>Fire Clasification</b>	Cfl-S1 1658-CPR-3137	
<b>Abz Nr.</b>	Z-156.601-1431	
<b>Pictures</b>	www.condorcontract.com	

## Floorsymbols



## Certificates

